

Portable Electric's VOLTstack® Equipment Run Times

		2k	5k	20k N.A. Split Phase	20k N.A. Three Phase
Battery (kWh)		2.8	5.6	80	80
Max Continuous Load (W)		2400	4800	20400	17200
Max Surge Rating 3 Sec (W)		4500	5800	30000	30000
Device	Power (W)	Time (hh:mm)	Time (hh:mm)	Time (hh:mm)	Time (hh:mm)
LED					
Cineo Matchstick	18	140:00	280:00	4444:30	4444:30
Cineo Matchbox	13	193:30	387:30	6154:00	6154:00
Cineo HS2	500	5:00	10:00	160:00	160:00
1x1 Astra LitePanel E Daylight/Bi-Color	30	84:00	168:00	2666:30	2666:30
1x1 Astra LitePanel EP Daylight/Bi-Color	55	45:30	91:30	1454:30	1454:30
1x1 Astra LitePanel Daylight/Bi-Color/Tungsten	110	23:00	45:30	727:00	727:00
Kino Celeb 200	100	25:00	50:00	800:00	800:00
Kino Celeb 250	145	17:00	34:30	552:00	552:00
Kino Celeb 400	210	12:00	24:00	381:00	381:00
Kino Celeb 450	255	10:00	19:30	314:00	314:00
Kino Celeb 850	575	4:00	8:30	139:00	139:00
Kino 800 mA Fluorescent	75	33:30	67:00	1066:30	1066:30
Kino Select 30/20	150	16:30	33:30	533:30	533:30
Arri Skypanel S-30C	200	12:30	25:00	400:00	400:00
Arri Skypanel S-60C	420	6:00	12:00	190:30	190:30
Arri Skypanel S-120C	400	6:00	12:30	200:00	200:00
Arri Skypanel S-360C	1500	1:30	3:00	53:30	53:30
LED Light Sheet (18 x 9 segments)	100	25:00	50:00	800:00	800:00
LED Strip Light (5m Reel)	13	193:30	387:30	6154:00	6154:00
CAMERA					
DIT Equipment	600	4:00	8:00	133:30	133:30
Video Village (Monitors/sound/charging)	800	3:00	6:00	100:00	100:00
Technocrane, Normal usage 20amp (continuous)	425	6:00	12:00	188:00	188:00
Fisher / Peewee Dolly (7 lifts per charge continuous)	425	6:00	12:00	188:00	188:00
TUNGSTEN					
150W pepper	150	16:30	33:30	533:30	533:30
300W Fresnel - Mole/Arri Brands	300	8:00	16:30	266:30	266:30
650W Fresnel (Tweenie)	650	4:00	7:30	123:00	123:00
1000W Fresnel	1000	2:30	5:00	80:00	80:00
2000W Arri T2	2000	1:00	2:30	40:00	40:00
2000W OpenFace (Blonde, Bluebell)	2000	1:00	2:30	40:00	40:00
5000W Arri T5	5000	N/A	N/A	16:00	16:00
10KW	10000	N/A	N/A	8:00	N/A
12KW Arri T12	12000	N/A	N/A	6:30	N/A
20KW Arri Mole Richardson	20000	N/A	N/A	4:00	N/A
24KW Arri T24	24000	N/A	N/A	N/A	N/A
HMI (BALLASTS)					
M8	800	3:00	6:00	100:00	100:00
M18	1821	1:00	2:30	44:00	44:00
M40	4000	N/A	1:00	20:00	20:00
M90	9000	N/A	N/A	9:00	9:00
ARRIMax 18	18000	N/A	N/A	4:30	N/A
18KW Silver Bullet Fresnel	18000	N/A	N/A	4:30	N/A